



**NOTES**

ALL DIMENSIONS IN MILLIMETRES.

THICKNESS OF LAYERS SHALL BE AS SPECIFIED IN THE CONTRACT.

ALL MATERIALS SHALL BE LAID IN CONFORMITY WITH THE RECOMMENDATIONS FOR LAYING, IN THE BRITISH STANDARD TO WHICH IT HAS BEEN MADE, OR IN ACCORDANCE WITH THE LAYING RECOMMENDATIONS IN BS EN 13108-4:2006

WHERE THE "TRIMMED" EDGE OF ANY EXCAVATION IS WITHIN 500mm OF THE ROAD EDGE, KERBING, OTHER FIXED FEATURES OR OTHER JOINTS, THE TRIM-LINE SHALL BE EXTENDED TO THE INTERFACE WITH THE ROAD EDGE, KERBING ETC. THE ADDITIONAL REINSTATEMENT AREA REQUIRED BY EXTENDING THE TRIM-LINE MAY BE CONFINED TO THE SURFACE COURSE, PROVIDED THE LOWER LAYERS HAVE NOT BEEN DAMAGED.

TACK COATS SHALL BE USED FOR BITUMINOUS MATERIALS UNLESS AS OTHERWISE DIRECTED BY THE ENGINEER.

ALL REINSTATEMENTS SHOULD BE UNDERTAKEN IN ACCORDANCE WITH THE LATEST EDITION OF THE NEW ROADS AND STREET WORKS ACT 1991.

East Lothian Council  
Road Services  
John Muir House  
Haddington  
East Lothian  
EH41 3HA



**PERMANENT REINSTATEMENT OF CARRIAGEWAY**

Date: SEPT 2013  
Scale: NTS

Drawn by:  
Checked by:

DRG. NO. 7300